

AD-A091 497

WOODWARD-CLYDE CONSULTANTS PLYMOUTH MEETING PA  
NATIONAL DAM INSPECTION PROGRAM. FLAT ROCK DAM  
AUG 80 M F BECK, J F FREDERICK


F/G 13/13  
NDS I.D. NUMBER--ETC(U)  
DACW31-80-C-0018


UNCLASSIFIED

NL

1 - 2

AD-A091 497





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS 1963-A

AD A091497

DELAWARE RIVER BASIN  
SCHUYLKILL RIVER  
MONTGOMERY AND PHILADELPHIA COUNTIES

PENNSYLVANIA  
NDS ID PA. 00896  
DER ID 51-1

1


10/12

# FLAT ROCK DAM

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

DACW 31-80-C-0018

This document has been approved  
for public release and sale; its  
distribution is unlimited.



DTIC  
ELECTE  
S NOV 10 1980 D  
A

Original contains color  
plates: All DTIC reproductions  
will be in black and  
white"

DEPARTMENT OF THE ARMY  
Baltimore District, Corps of Engineers  
Baltimore, Maryland 21203

AUGUST 1980

DOCUMENT IS BEST QUALITY PRACTICABLE.  
THE COPY FURNISHED TO DDC CONTAINED  
SIGNIFICANT NUMBER OF PAGES WHICH DO NOT  
REPRODUCE FAIRLY.

8011 03 047

DDC FILE COPY

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**

DELAWARE RIVER BASIN

⑥ National Dam Inspection Program.

FLAT ROCK DAM, MONTGOMERY AND PHILADELPHIA COUNTIES,  
PENNSYLVANIA

Number

(NDS I.D. 51-1) PA 00896,  
DER I.D. 51-1)


Schuylkill River, Montgomery and  
Philadelphia Counties, Pennsylvania.

PHASE I INSPECTION REPORT

NATIONAL DAM INSPECTION PROGRAM

⑩ Mary F. / Eeck

John E. / Hendrick



⑪ Aug 80

⑫ 102

⑮

DNRN 31-80-C-0018

Prepared by:

WOODWARD-CLYDE CONSULTANTS  
5120 Butler Pike  
Plymouth Meeting, Pennsylvania 19462

Submitted to:

DEPARTMENT OF THE ARMY  
Baltimore District, Corps of Engineers  
Baltimore, Maryland 21203

AUGUST 1980

"Original contains color  
plates: All DDC reproductions  
will be in black and  
white"

394157

AB

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams for Phase I Investigations. Copies of these guidelines may be obtained from the Office of the Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to expeditiously identify those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigations, testing and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify the need for more detailed studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected, and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	<input type="checkbox"/>
Per Form 50	
Distribution/	
Availability Codes	
Avail and/or	
Dist Special	
A 23	

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

Name of Dam: Flat Rock Dam  
County Located: Montgomery and Philadelphia  
Counties  
State Located: Pennsylvania  
Stream: Schuylkill River  
Coordinates: Latitude 40° 2.4'  
Longitude 75° 14.9'  
Date of Inspection: June 11, 1980

Flat Rock Dam is owned by the Commonwealth of Pennsylvania, and the pool formed is used primarily for recreational purposes. The left abutment of the dam abuts the Manayunk Canal wall owned by the City of Philadelphia. Visual inspection of the exposed sections of the dam, review of available data and simplified calculations presented in Appendix D indicate the dam is in good condition. No data other than Plate 12, Appendix E, were available for the canal wall. Calculations presented in Appendix G indicate the wall is marginally stable under assumed conditions. The results of the stability analysis are at variance with the canal wall's demonstrated performance history.

In accordance with criteria established by Federal (OCE) Guidelines, the recommended spillway design flood for this "Intermediate" size dam and "High" hazard potential classification is the Probable Maximum Flood (PMF).

Calculations presented in Appendix D indicate the structure will pass about 0.07 PMF without overtopping the right embankment. As the spillway will not pass the PMF without overtopping, it is considered to be "Inadequate". It is considered that the dam is not likely to fail; therefore, the spillway is not considered to be "Seriously Inadequate".

It is recommended that the following measures concerning the canal wall be undertaken immediately by the City of Philadelphia. Items (1) and (2) should be performed under the supervision of a registered professional engineer experienced in the design and construction of dams.

- (1) As the canal wall stability analysis presented in Appendix G is at variance with its demonstrated performance history, further investigations should be made to verify the configuration of the section, assumed foundation and canal bottom conditions, and results of the analysis. If stability of the wall

Flat Rock Dam, NDS ID PA 00896


cannot be demonstrated, measures should be taken to insure its stability under all expected conditions.

- (2) Seepage through the canal wall should be monitored and evaluated.
- (3) Surficial deteriorated concrete on the canal wall should be repaired.
- (4) In conjunction with Item (3), all open cracks at the top of the wall at the construction joints should be sealed to prevent damage from freezing water in the winter.

An operation and maintenance manual for small dams has been prepared by the Department of Environmental Resources, Division of Completed Projects, Bureau of Operations. Portions of this manual apply to Flat Rock Dam. It is important that persons concerned with this structure be familiar with the procedures contained in the manual. The City of Philadelphia should develop a maintenance procedure to insure the canal wall is maintained in the best possible condition. Since the Schuylkill River is covered under the National Weather Service Flood Forecasting Service and procedures have been established to warn of potential flooding along the river downstream of the dam, it is not recommended that a separate warning procedure be developed for this structure.


Mary F. Beck  
Mary F. Beck, P.E.  
Pennsylvania Registration 27447E  
Woodward-Clyde Consultants

8/8/80  
Date



John H. Frederick, Jr.  
John H. Frederick, Jr., P.E.  
Maryland Registration 7301  
Woodward-Clyde Consultants

8/8/80  
Date



APPROVED BY:

James W. Peck  
JAMES W. PECK  
Colonel, Corps of Engineers  
District Engineer

5 Sep 80  
Date





**OVERVIEW**  
**FLAT ROCK DAM, MONTGOMERY AND PHILADELPHIA COUNTIES, PENNSYLVANIA**

## TABLE OF CONTENTS

	<u>PAGE</u>
Preface	i
Assessment and Recommendations	ii
Overview Photograph	iv
 <b>SECTION 1 - PROJECT INFORMATION</b>	
1.1 General	1
1.2 Description of Project	1
1.3 Pertinent Data	4
 <b>SECTION 2 - ENGINEERING DATA</b>	
2.1 Design	6
2.2 Construction	6
2.3 Operational Data	6
2.4 Evaluation	7
 <b>SECTION 3 - VISUAL INSPECTION</b>	
3.1 Findings	8
3.2 Evaluation	10
 <b>SECTION 4 - OPERATIONAL PROCEDURES</b>	
4.1 Procedures	11
4.2 Maintenance of the Dam	11
4.3 Maintenance of Operating Facilities	11
4.4 Warning Systems In Effect	11
4.5 Evaluation	11
 <b>SECTION 5 - HYDROLOGY/HYDRAULICS</b>	
5.1 Evaluation of Features	12
 <b>SECTION 6 - STRUCTURAL STABILITY</b>	
6.1 Evaluation of Structural Stability	15
 <b>SECTION 7 - ASSESSMENT/REMEDIAL MEASURES</b>	
7.1 Dam Assessment	17
7.2 Remedial Measures	17
 <b>APPENDIX</b>	
A Visual Inspection	
B Engineering Data, Design, Construction and Operation	
C Photographs	
D Hydrology/Hydraulics	
E Plates	
F Geology	
G Stability Analysis	

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM  
FLAT ROCK DAM  
NATIONAL ID NO. PA 00896  
DER NO. 51-1

SECTION 1  
PROJECT INFORMATION

1.1 General.

a. Authority. The Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of dams throughout the United States.

b. Purpose. The purpose of the inspection is to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project.

a. Dam and Appurtenances. Flat Rock Dam is a run-of-the-river dam across the Schuylkill River. It is a concrete gravity structure with a 510 foot ogee spillway section and a spillway crest elevation of 37.7 throughout most of its length. The right abutment is in the right river bank, while the left abutment abuts the previously existing Manayunk Canal wall.

The ogee gravity spillway has a base width of 34 feet, and the total height from the minimum foundation elevation to the crest of the non-overflow section at the right abutment is about 36 feet. Two 60 foot long sections of the spillway crest, one near each of the abutments, are 0.5 foot lower than the rest of the spillway to form low flow sections. The spillway has a short apron, which discharges flow directly onto the river bed. The height of the spillway crest sections above the downstream apron is 14.7 feet, while the top of the right abutment is 21.2 feet above the adjacent spillway apron. The foundation was grouted, and rock anchors are located in the heel of the dam, as shown on Plates 5 and 9, Appendix E.

The dam was constructed about 12 feet downstream, at the right abutment, of the previously existing rock filled timber crib dam. The new right retaining wall was constructed downstream of the stone masonry abutment. The old abutment

extends about 65 feet into the right river bank, Plate 4, Appendix E. The abutment slope behind the new retaining wall and downstream of the old abutment is protected with grouted derrick stone over compacted rock fill.

The left abutment for the timber crib dam is of stone masonry at the entrance to the Manayunk Canal, Photograph 4. The upstream end of the concrete canal wall abuts the downstream end of the stone abutment. The left abutment for Flat Rock Dam, Plate 9, adjoins the previously existing canal wall and is anchored to the canal wall by No. 8 bars grouted into the existing masonry and concrete wall.

The canal wall, a concrete gravity structure, extends approximately 800 feet between the left abutment of the dam and the canal feeder house. The canal wall top width is 15 feet in the vicinity of the abutment and about six feet elsewhere. Throughout its length, the top of the canal wall is stepped in sections, with top elevations ranging from 42.5 to 49.9. At approximately the midpoint between the dam and the feeder house is an 87 foot wide weir at a crest elevation of 39.0. The maximum height of the canal wall above the river bed is about 29 feet adjacent to the dam. The canal bottom ranges from elevation 25 to 37.

The canal has not been used for navigation since 1917, but within the past few years was restored to a limited extent for a public park. The upstream entrance has a sheet piling cutoff wall in the vicinity of the feeder house. The feeder house has been burned and the gates are no longer operational. The towpath was renovated to a bicycle path. A new weir was installed between the old lock walls about two miles downstream to maintain the canal water level.

b. Location. Flat Rock Dam is located on the Schuylkill River approximately 2.9 miles upstream of U.S. Route 1. The dam is located in Montgomery and Philadelphia Counties, Pennsylvania. The dam site and reservoir are shown on USGS Quadrangle entitled "Germantown, Pennsylvania" at coordinates N 40° 2.4' W 75° 14.9'. A regional location plan of the dam is enclosed as Plate 1, Appendix E.

c. Size Classification. The dam is classified as an "Intermediate" size structure by virtue of its estimated 1,500 acre-foot total storage capacity and less than 100 foot height.

d. Hazard Classification. A "High" hazard classification is assigned consistent with the potential for property damage and possible loss of life along the Schuylkill River in the event of sudden failure of the dam.

e. Ownership. The dam is owned by the Department of Environmental Resources. All correspondence should be addressed to Bureau of Operations, Department of Environmental Resources, Post Office Box 1467, Harrisburg, Pennsylvania 17120. The canal wall is owned by the City of Philadelphia. Correspondence concerning the canal wall should be addressed to the Water Department, Municipal Services Building, Philadelphia, Pennsylvania 19107.

f. Purpose of Dam. The reservoir formed by the dam is used for recreational purposes and forms a desilting basin.

g. Design and Construction History. The original Flat Rock Dam was a rock fill timber crib structure started in 1815, by the Schuylkill Navigation Company as part of the transportation system to float barges between Philadelphia and the upper reaches of the Schuylkill River. A cornerstone in the canal wall near the feeder house is dated 1883. The Reading Railroad Company acquired the canal properties from the Schuylkill Navigation Company about 1890. The east (left) abutment of the dam and the lock chambers were rebuilt of concrete and stone masonry during the time the railroad company owned and operated the canal. Canal operations ceased in 1917, and in April 1947, the railroad company conveyed most of their canal holdings to the Commonwealth of Pennsylvania.

By 1952, inspections concluded that the stability of the timber crib dam was in question, and extensive repairs were required. As the City of Philadelphia used the reservoir as a water intake at the Shawmont Pumping Station, negotiations were begun in 1954, with the intent to transfer ownership of the dam and canal to the city. In July 1957, ownership of the canal, including the feeder house and canal wall, was transferred to the City of Philadelphia. On April 24, 1972, an application for a permit to reconstruct Flat Rock Dam was made. The issuing of the permit was held up for more than two years because of a dispute between different state agencies about provisions in the design for a fish passage facility for future shad migration in the Schuylkill River. The matter was resolved by acknowledging that fishway facilities may be necessary in the future. The "Report Upon the Application of the Office of Resource Management, Department of Environmental Services" was prepared by the Division of Dams and Encroachments, July 16, 1974. The permit was issued October 8, 1974, and in June 1975, Pettinaro Construction Company, Inc., was contracted by the General State Authority to build the new dam.

There are no documents in DER files regarding the construction of the dam. However, the as-built drawings give limited indications of the construction details of Flat Rock

Dam. Two sluice gates, ten feet by eight feet, together with trash rack and stop log structures were initially proposed to be built at the canal wall location, but were subsequently deleted from the design. The old timber crib dam was left in place during construction of the new concrete gravity dam. Reportedly, concrete blocks were used on top of the dam to divert water around through the canal wall. Two 30 inch corrugated metal pipes were used for diversion during construction of the right half of the dam. Upon completion of the dam, the pipes were grouted full. The top of the timber crib dam was removed to elevation 32.5. There are two dam completion certificates in the file: one dated October 6, 1977, and one dated December 20, 1977.

h. Normal Operating Procedures. All water flows over the weir of the dam. When the river level upstream of the dam increases to an elevation about 1.3 feet above the dam crest, water is also discharged into the river through the 87 foot long weir through the canal wall, shown on Photograph 6.

### 1.3 Pertinent Data.

A summary of pertinent data for Flat Rock Dam is presented as follows.

a.	Drainage Area (square miles)	1,809 <sup>(1)</sup>
b.	Discharge at Dam Site (cfs)	
	Maximum Flood (Tropical Storm Agnes, 1972, measured at downstream gaging station)	103,000
	At Top of Right Abutment	30,000
c.	Elevation (feet above MSL)	
	Top of Dam	
	Right Abutment	44.2
	Left Abutment	44.8
	Spillway Crest	
	Low Flow Sections (total 120 feet long)	37.2
	Main Spillway (total 390 feet)	37.7
	Downstream Apron (toe)	23.0
	Tailwater (6/10/80)	22.7±
	Riverbed	19.0 to 23.0
	Minimum Foundation	8 ±

(1) Information obtained from DER, Water Resources Bulletin 4, "Water Resources Survey, The Schuylkill River, Pennsylvania".

d.	Reservoir (miles)	
	Length at Normal Pool	4.4 <sup>(1)</sup>
	Fetch at Normal Pool (est)	1.5
e.	Storage (acre-feet)	
	Normal Pool	788 <sup>(2)</sup>
	At Top of Non-overflow (est)	1,500
f.	Reservoir Surface (acres)	
	Normal Pool	105 <sup>(2)</sup>
g.	Dam Data	
	Type	Concrete gravity overflow dam
	Length (overflow)	510 feet
	Height (above downstream apron)	21.2 feet
	Cutoff	Keyed where necessary to find sound rock
	Grout Curtain	Grouted under heel
h.	Spillway	
	Type	Ogee weir
	Elevation	37.7 feet
	Low Flow Notches	37.2 feet
	Length	510 feet
	Reservoir Drain	None
i.	Canal Wall	
	Type	Concrete and masonry gravity
	Length	800 feet
	Top Elevation	42.5 to 49.9 feet
	Top Width	6.0 to 15.5 feet
	Spillway	
	Type	Weir
	Size	87 feet
	Elevation	39.0 feet

(1) See footnote on previous page.

(2) From "Application Report" prepared by the state, July 16, 1974.

## SECTION 2 ENGINEERING DATA

### 2.1 Design.

a. Data Available. A summary of engineering data for Flat Rock Dam is presented in the checklist attached as Appendix B. Principal documents containing pertinent data used for this report include the "Report Upon the Application of the Office of Resources Management, Department of Environmental Resources" dated July 16, 1974, as-built drawings, stability calculations and a summary of hydraulic calculations supplied by the Bureau of Design. Other data used to evaluate the engineering characteristics of the dam include the Water Resources Bulletin, Bulletin No. 4, "Water Resources Survey, The Schuylkill River, Pennsylvania", prepared for the Commonwealth of Pennsylvania by E. H. Bourquard & Associates, dated March 1968, and Bulletin No. 9, "Hydrologic Data of the June 1972 Flood in Pennsylvania", prepared in cooperation with the U.S. Department of the Interior, Geological Survey, August 1974.

b. Design Features. Principal design features are illustrated on the plan, profile and cross-section plates of this structure and are enclosed in Appendix E as Plates 2 through 10. These plates are reproduced from as-built drawings supplied by the Bureau of Operations, Pennsylvania Department of Environmental Resources (DER). A description of the design features is presented in Section 1.2, entitled "Description of Project".

### 2.2 Construction.

A limited description of the construction history is presented in Section 1.2.

### 2.3 Operational Data.

There are no operational records maintained. Since all flow passes over the overflow section, there are no minimum flow requirements downstream.



#### 2.4 Evaluation.

a. Availability. All engineering data reproduced in this report and studied for this investigation were provided by the Pennsylvania DER, Bureau of Dams and Waterways Management, Bureau of Completed Projects and Bureau of Design.

b. Adequacy. Data included in Division of Dam Safety files and information received from various state representatives were not sufficiently adequate to evaluate the design features of the dam and appurtenant structures in accordance with Phase I guidelines.

c. Validity. There is no reason to question the validity of the available data.

### SECTION 3 VISUAL INSPECTION

#### 3.1 Findings.

a. General. Observations and comments of the field inspection team are contained in the checklist enclosed herein as Appendix A, and are summarized and evaluated as follows. In general, the ogee section, right and left abutments, and the canal wall appear to be in good condition. At the time of the inspection, the river was flowing at a normal rate over the spillway and, thus, the ogee section and downstream apron of the spillway could not be inspected.

b. Dam. The exposed portions of Flat Rock Dam are extremely limited and consist of the right gravity wall and the left abutment adjoining the previously existing canal wall. At the right end of the dam, both the previously existing masonry abutment and the new concrete gravity abutment appear to be in good condition. There was no distortion in alignment that would be indicative of movement of the foundation. No concrete spalling or excessive deterioration or cracking was noted, although there are some leachate deposits on the concrete gravity wall downstream of the weir. The grouted riprap, both upstream and downstream of the dam centerline, appears to be in place and in good condition.

The left abutment is tied into the previously existing canal wall by No. 8 reinforcing anchor bars grouted into the wall. The exposed concrete surfaces were inspected, and no spalling, excessive concrete cracking or other concrete deterioration were noted. Leachate deposits were noted on the riverside face of the left abutment.

#### c. Appurtenant Structures.

1. Ogee Spillway. About one foot of water was flowing over the ogee weir at the time of the inspection. Water flowing over the spillway crest was smooth, with no indications of cracks or displacement between monoliths.

2. Canal Wall. The elevation of the canal wall ranges from a high of about 49.9 feet near the feeder house to a low of 42.5 near its midpoint. As shown on Sheet 5C of 11, Appendix A, the wall is divided into four sections of different elevations separated by steps, with the top of the wall being at nearly constant elevations within each section. The top width ranges from about 6.0 feet to a maximum of about

15 feet. The canal side face appears to be vertical, while the riverside of the wall is nearly vertical for the top several feet and then has a batter of about 0.4H:1V. About 490 feet downstream of the dam centerline is an 87 foot wide weir through the canal wall; see Photograph 6. At the time of the inspection, the canal water level was about four inches below the weir crest.

The riverside face of the canal wall displays leachate deposits over its entire length. Some seepage was also observed on the downstream river face of the wall. Spalls and concrete deterioration have occurred at both vertical and horizontal construction joints of the wall. Spalling on the top of the wall has typically occurred at the construction joints; see Photographs 5, 6 and 10.

At the left abutment of Flat Rock Dam, the canal wall is 15.25 feet wide. There is some vertical displacement at the construction joint where the 15.25 foot section joins the 6 foot section, apparently as constructed; see Photograph 11. The extreme upstream portion of the canal wall is the original stone masonry abutment to the old Flat Rock Dam. The stone masonry appears to be structurally sound.

d. Reservoir. At the time of the inspection, the impounding area was at normal pool, and slopes to the water's edge appear well vegetated and stable. It is reported that the water is 15 feet deep upstream of the dam.

e. Downstream Channel. The natural channel below the dam is the Schuylkill River, which appears to be in good condition with stable banks and a minimum amount of scour or deposition. Venice Island, downstream of the dam, is occupied primarily by industrial complexes. The minimum height of the bank above the water level at the northwest end of the island is about 16.5 feet, or an elevation of approximately 39.4 feet. The difference between the top of the bank and the river appears fairly constant all the way down to Green Lane Bridge. The occupied building closest to the river level is a canoe clubhouse approximately 2.8 miles downstream of the dam at the confluence of the Wissahickon Creek and the Schuylkill River. The first floor of the house is about 15 feet above the river surface. About seven miles downstream of Flat Rock Dam is Fairmount Dam. Immediately upstream of Fairmount Dam is Boathouse Row, where there are 11 boathouses built at the water's edge. The pool above Fairmount Dam is used extensively for recreational purposes, and parks are on both sides of the river upstream of the dam. Sudden failure of Flat Rock Dam not during an extreme event would create the possibility for many lives lost; therefore, the dam warrants a "High" hazard potential classification.

### 3.2 Evaluation.

Inspection of the dam and abutments disclosed no evidence of apparent past or present movement that would indicate existing instability of the concrete dam. Since flow was passing over the spillway at the time of the inspection, the toe of the spillway could not be inspected for undermining, scour or the condition of the apron or bedrock immediately downstream.

Inspection of the canal wall disclosed surficial concrete deterioration of the top and the downstream face. Construction joint deterioration is occurring within the canal wall as evidenced by leachate deposits on the riverside of the wall. There is no evidence detected by visual inspection that the structural integrity of the wall has been affected. In summary, the dam and canal wall are considered to be in good condition, with the canal wall requiring repairs to the concrete.

## SECTION 4 OPERATIONAL PROCEDURES

### 4.1 Procedures.

Operation of the dam does not require a dam tender. All flow discharges directly over the ogee section and downstream into the Schuylkill River.

### 4.2 Maintenance of the Dam.

The dam is inspected yearly by the Department of Environmental Resources (DER), Bureau of Operations, in Harrisburg. The local Schuylkill River Project office provides routine maintenance of the structure, which includes removal of debris, painting and sealing of any surficial cracks. There was no evidence or acknowledgement of maintenance of the canal wall by the City of Philadelphia.

### 4.3 Maintenance of Operating Facilities.

There are no mechanical devices or operating facilities to maintain for this structure.

### 4.4 Warning Systems In Effect.

According to DER's representative during the time of the inspection, there are no formal warning procedures associated with Flat Rock Dam. The Schuylkill River is covered by the National Weather Service flood forecasting service. When flooding is expected, reports are broadcast on the NOAA radio service, provided to the national wire services, and the City of Philadelphia Emergency Coordinator is notified.

### 4.5 Evaluation.

Since there are no operating facilities and since the dam does not require a dam tender, it is judged that the current operating procedure is a satisfactory method of operating the dam.

## SECTION 5 HYDROLOGY/HYDRAULICS

### 5.1 Evaluation of Features.

a. Design/Evaluation Data. No original design data were located. Summary hydraulic data were supplied by DER, Bureau of Design, and additional calculations for this investigation are presented in Appendix D.

The large watershed is about 78 miles long and ranges from about 22 to 32 miles wide, having a total drainage area of 1,809 square miles above Flat Rock Dam. The Schuylkill River Watershed at its mouth drains an area of approximately 1,920 square miles. Elevations range from a high of 1,750 feet in the extreme upper reaches to 37.7, the weir elevation at Flat Rock Dam. From the headwaters at Tuscarora Springs in Schuylkill County to Flat Rock Dam, the river travels approximately 115 miles. The river passes through four major physiographic provinces in Pennsylvania, ranging from the Appalachian Ridge and Valley Province to the Atlantic Coastal Plain. Thus, the hydrology and stream flows of the Schuylkill River Watershed vary widely at different points along the river because of the varying topographic and climatological conditions along the river course. In general, higher average rainfalls and steeper topography in the northern provinces of the river above the Blue Ridge physiographic province (above Port Clinton, Pennsylvania) produce slightly greater average runoffs per square mile than those observed in the lower portions of the watershed. In addition, localized storms or short-term droughts may not be general over the entire basin.

The concrete ogee weir was designed based on a design head of 14.5 feet or a discharge of 98,000 cfs. Summary data provided indicates flows of 50,000 cfs will partially submerge the weir and, for flows exceeding 130,000 cfs, the tailwater elevation will equal the upstream water surface level.

In accordance with criteria established by Federal (OCE) Guidelines, the recommended spillway design flood for this "Intermediate" size dam and "High" hazard classification is the Probable Maximum Flood (PMF).

b. Experience Data. Reservoir water levels are not maintained for this dam. Large flows, such as Tropical Storm Agnes in June 1972, flood out Venice Island so that the industrial complex about one mile below the dam is also

flooded. Maximum river elevations during Tropical Storm Agnes are reported as 43.0 downstream of the dam (river mile 14.75) and 51.0 upstream of the dam (river mile 15.95). Flat Rock Dam is about river mile 15.75.

c. Visual Observations. On the date of the inspection, there were no conditions observed that would indicate a reduced spillway capacity during an extreme event. Observations regarding the condition of the downstream channel, spillway and reservoir are located in Appendix A and discussed in greater detail in Section 3.

d. Overtopping Potential. Because of the large drainage area above Flat Rock Dam, and because Flat Rock Dam is a run-of-the-river dam with limited flood storage capacity behind it compared to its large drainage area, along with the fact that the weir will be submerged during high flows, it is believed that an overtopping analysis is not significant for this structure. During a large storm, there is little attenuation of the inflow hydrograph by the available flood storage.

The spillway is capable of discharging about 30,000 cfs without overtopping the right abutment. The estimated tailwater elevation for flows of 50,000 cfs is 38.6, higher than the weir crest. It is estimated that storms of about 0.07 PMF will overtop the right abutment, considered to be the top of the dam. Flows greater than about 0.11 PMF, or 50,000 cfs, will have a tailwater elevation approximately equal to the weir crest. Flows greater than these values will begin to submerge the weir and reduce the weir capacity, shown in Appendix D. The Spillway Design Flood (SDF) hydrograph presented in Appendix D was supplied by the Corps of Engineers, Philadelphia District, and is assumed to equal 0.5 PMF. The estimated peak SDF inflow is about 225,700 cfs, greater than the estimated 100,000 cfs at Flat Rock Dam during Tropical Storm Agnes in June 1972. During Tropical Storm Agnes, it was reported that Venice Island downstream of the dam was flooded, and the canal wall and the whole dam was submerged.

e. Spillway Adequacy. As the spillway will not pass the PMF without overtopping the abutment, the spillway is rated as "Inadequate". As overtopping is estimated not to cause failure, the spillway is not rated "Seriously Inadequate".

f. Downstream Conditions. Between Flat Rock Dam and Fairmount Dam, seven river miles downstream, there are a limited number of permanent structures located within 16 feet of the top of the water. The canoe clubhouse is located 15 feet above the water at the confluence of the Wissahickon Creek and the Schuylkill River, and there are 11 boathouses located immediately upstream of Fairmount Park at the water level. During a large storm, it is unlikely that any of these structures would be occupied. However, Flat Rock Dam is located within an urban area and above a stretch of water that is heavily used for recreational purposes, boating and fishing, and parks are located along the river banks on both sides. Thus, the greatest potential to loss of life during failure of the dam would result from failure not occurring as a result of a large storm, justifying a "High" hazard potential rating.



## SECTION 6 STRUCTURAL STABILITY

### 6.1 Evaluation of Structural Stability.

a. Visual Observations. Visual observations detected no evidence of existing or pending instability of the right abutment, weir or left abutment of the dam. There was no distortion along the spillway crest to infer excessive scour downstream, monolith displacement or structural deterioration of the ogee section. However, the entire ogee section was covered with water and could not be thoroughly inspected. The 800 foot long canal wall was also inspected. Surficial concrete deterioration, spalling and cracking were noted on the top of the wall and along the river face of the wall. Some seepage and leachate deposits were also noted on the downstream face of the wall. Although concrete joint deterioration is occurring within the canal wall, as evidenced by the leachate deposits and seepage, there is no evidence detected by visual inspection that the structural integrity of the structure has been affected.

b. Design and Construction Data. Stability calculations for Flat Rock Dam were available. A stability analysis was performed on the dam itself based on a head of water 19.3 feet above the weir, or 167,000 cfs, and a tailwater depth based on Manning's Formula on the downstream channel. As-built drawings indicate that the dam is anchored to the underlying bedrock by rock anchors. The stability analysis results are summarized in Appendix G.

The stability analysis of the canal wall presented in Appendix G indicates adequate resistance to sliding under an assumed pool level. Neglecting tailwater in the overturning analysis indicates an unstable structure, while including the tailwater indicates a marginally stable structure. These results are at variance with the demonstrated performance of the dam during large events, such as Tropical Storm Agnes, June 1972, when the pool level exceeded the pool level used in the stability analysis.

c. Operating Records. There are no operational records for this structure.

d. Post-Construction Changes. Since the completion of the dam in 1977, there have been no modifications made to this structure.

e. Seismic Stability. The dam is located in Seismic Zone 1. Normally it can be considered that if a dam in this zone is stable under static conditions, it can be assumed safe for any expected earthquake conditions. As the dam is assessed to be stable under present static loading conditions, it can reasonably be assumed to be stable under seismic loading conditions. However, since the static stability of the canal wall is questionable, its seismic stability is also in doubt.

## SECTION 7 ASSESSMENT/REMEDIAL MEASURES

### 7.1 Dam Assessment.

a. Evaluation. Visual inspection of the exposed sections of the dam and review of the limited available data indicate that Flat Rock Dam is in good condition. It is to be noted that the entire spillway and apron were submerged and could not be inspected; therefore, a complete visual assessment of the structure could not be performed. The canal wall was also inspected. Construction joint deterioration is occurring through the canal wall, as evidenced by leachate deposits and damp areas. There was no evidence detected by visual inspection that the structural integrity of the structure has been affected. Therefore, although repairs are required, the canal wall is considered to be in good condition.

In accordance with criteria established by Federal (OCE) Guidelines, the recommended spillway design flood for this "Intermediate" size dam and "High" hazard potential classification is the Probable Maximum Flood (PMF).

Calculations presented in Appendix D indicate the structure will pass about 0.07 PMF without overtopping the right embankment. As the spillway will not pass the PMF without overtopping, it is considered to be "Inadequate". It is considered that the dam is not likely to fail; therefore, the spillway is not considered to be "Seriously Inadequate".

b. Adequacy of Information. Information available for this investigation, the visual inspection, and simplified calculations presented in Appendices D and G were sufficient to indicate that no further investigations are required for the dam, but additional stability analysis is required for the canal wall.

c. Urgency. The recommendations presented in the following section should be implemented immediately.

### 7.2 Remedial Measures.

a. Facilities. It is recommended that the following measures concerning the canal wall be undertaken immediately by the City of Philadelphia. Items (1) and (2) should be performed under the supervision of a registered professional engineer experienced in the design and construction of dams.

- (1) As the canal wall stability analysis presented in Appendix G is at variance with its demonstrated performance history, further investigations should be made to verify the configuration of the section, assumed foundation and canal bottom conditions, and results of the analysis. If stability of the wall cannot be demonstrated, measures should be taken to insure its stability under all expected conditions.
- (2) Seepage through the canal wall should be monitored and evaluated.
- (3) Surficial deteriorated concrete on the canal wall should be repaired.
- (4) In conjunction with Item (3), all open cracks at the top of the wall at the construction joints should be sealed to prevent damage from freezing water in the winter.

b. Operation and Maintenance Procedures. An operation and maintenance manual for small dams has been prepared by the Department of Environmental Resources, Division of Completed Projects, Bureau of Operations. Portions of this manual apply to Flat Rock Dam. It is important that persons concerned with this structure be familiar with the procedures contained in the manual. The City of Philadelphia should develop a maintenance procedure to insure the canal wall is maintained in the best possible condition. Since the Schuylkill River is covered under the National Weather Service Flood Forecasting Service and procedures have been established to warn of potential flooding along the river downstream of the dam, it is not recommended that a separate warning procedure be developed for this structure.

**APPENDIX**

**A**

CHECK LIST  
VISUAL INSPECTION  
PHASE I

Sheet 1 of 11

Name Dam Flat Rock Dam County Philadelphia State Pennsylvania National ID # PA 00896  
Type of Dam Concrete gravity Hazard Category High  
Date(s) Inspection 6/9/80 Weather Sunny Temperature 60's

Pool Elevation at Time of Inspection 38.8 M.S.L. Tailwater at Time of Inspection 22.7± M.S.L.

Inspection Personnel:

Mary F. Beck (Hydrologist) Richard E. Mabry Civil (Geotechnical/)  
David Chou (Structural) Vincent McKeever (Hydrologist)  
Raymond S. Lambert (Geologist)

Mary F. Beck Recorder

Remarks:

John Smith, Lock 60 Montclair, and Clifford Romig, Harrisburg, Bureau of Operations, were  
on site and provided assistance to the inspection team.

# CONCRETE/MASONRY DAMS

## GUIDE WALL

Sheet 2 of 11

VISUAL EXAMINATION OF		REMARKS OR RECOMMENDATIONS	
ANY NOTICEABLE SEEPAGE	OBSERVATIONS	DAM	CANAL WALL
	No seepage noticed. Leachate deposits were noted on both the right gravity wall and left abutment.		Leachate deposits visible and some seepage, see photographs, on river side of wall.
STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS	Structure built and completed in 1977. No deterioration observed.		Old masonry abutment remains structurally sound. The concrete abutment built prior to 1947 shows deterioration at horizontal joints.
DRAINS	None		None
WATER PASSAGES	None		None
FOUNDATION			

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	DAM	OBSERVATIONS	Sheet 3 of 11	
			CANAL WALL	REMARKS OR RECOMMENDATIONS

SURFACE CRACKS  
CONCRETE SURFACES

Water overflowing the spillway; no observation can be made.

A lot of spalled areas on the top of canal wall. Most of them are located at vertical construction joints. Several spalled areas are also found on the river face of wall near the water level.

STRUCTURAL CRACKING

Some shrinkage cracks at the new abutment but not serious.

Some shrinkage cracks on top of the canal wall, but they probably have been there for years.

VERTICAL AND HORIZONTAL  
ALIGNMENT

See Sheets 5B and 5C.

MONOLITH JOINTS

CONSTRUCTION JOINTS

Typically spillings occur at the vertical joints of the wall. Some leaching at the horizontal joint of river face of wall. Canal face is under the water.



EMBANKMENT

Sheet 4 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	N/A	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	N/A	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	N/A	
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	N/A	
RIPRAP FAILURES	N/A	

EMBANKMENT

Sheet 5 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

JUNCTION OF EMBANKMENT  
AND ABUTMENT, SPILLWAY  
AND DAM

N/A

ANY NOTICEABLE SEEPAGE


N/A


STAFF GAGE AND RECORDER

N/A



DRAINS

N/A





LOOKING UPSTREAM



FIELD OBSERVATION PROFILE  
CONCRETE WALL ON EAST BANK  
OF SCHUYLKILL RIVER  
FLAT ROCK DAM  
SHEET 5C OF 11

OUTLET WORKS

DAM	GUIDE WALL	Sheet 6 of 11
VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	Dam has no outlet works.	Water level in canal controlled by gates in control building and sheet pile cutoff (see sheet 5A).
INTAKE STRUCTURE		Brick control building was burned but masonry appears sound.
OUTLET STRUCTURE		Same as above.
OUTLET CHANNEL		Water is discharged into canal.
EMERGENCY GATE		No gates appear operational. One gate partly open.

UNGATED SPILLWAY

DAM	GUIDE WALL	Sheet 7 of 11
VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	Weir completely under water, flow appeared uniform.	Concrete has spalled off weir crest.
APPROACH CHANNEL	None	None
DISCHARGE CHANNEL	Discharges into Schuylkill River.	Discharges into Schuylkill River.
BRIDGE AND PIERS	None	None

GATED SPILLWAY

Sheet 8 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SILL	None	
APPROACH CHANNEL	N/A	
DISCHARGE CHANNEL	N/A	
BRIDGE AND PIERS	N/A	
GATES AND OPERATION EQUIPMENT	N/A	



INSTRUMENTATION

		Sheet 9 of 11
VISUAL EXAMINATION	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
MONUMENTATION/SURVEYS	None known.	
OBSERVATION WELLS	None	
WEIRS	None	
PIEZOMETERS	None	
OTHER	None	

RESERVOIR

Sheet 10 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

SLOPES

*The upstream river slopes are flat to moderate.*

SEDIMENTATION

*It was reported by Mr. Smith that little sediment has accumulated upstream of the dam.*

DOWNSTREAM CHANNEL

Sheet 11 of 11

## REMARKS OR RECOMMENDATIONS

## OBSERVATIONS

## VISUAL EXAMINATION OF

CONDITION  
(OBSTRUCTIONS,  
DEBRIS, ETC.)

*The Schuylkill River downstream of the dam has a rock bed. The banks appear stable with a minimum about of scour or deposition.*

## SLOPES

*The valley gradient is on the order of 0.001*

APPROXIMATE NO.  
OF HOMES AND  
POPULATION

*Immediately downstream of the dam is an island on which there are several industrial complexes located about 16.5 feet above water level at the time of inspection. About 2.8 miles downstream of the dam is a clubhouse located about 15 feet above water level. About seven miles downstream of Flat Rock Dam is Fairmont Dam, above which is boathouse row. About 10 boathouses are built at the water's edge.*

**APPENDIX**

**B**

CHECK LIST  
ENGINEERING DATA  
DESIGN, CONSTRUCTION, OPERATION  
PHASE I

NAME OF DAM Flat Rock Dam  
ID # PA 00886

Sheet 1 of 4

ITEM

REMARKS

AS-BUILT DRAWINGS

*On file with Bureau of Operations and provided  
for this investigation*

REGIONAL VICINITY MAP

*Plate 1, Appendix E.*

CONSTRUCTION HISTORY

*See text, Section 1.2.*

TYPICAL SECTIONS OF DAM

*Appendix E.*

OUTLETS - PLAN

DETAILS

*Appendix E.*

CONSTRAINTS

DISCHARGE RATINGS

*Appendix D.*

RAINFALL/RESERVOIR RECORDS

*National Weather Service Rain Gaging Stations  
within watershed. No reservoir records maintained  
for this dam.*

ITEM	REMARKS
DESIGN REPORTS	<i>None available.</i>
GEOLOGY REPORTS	<i>See Appendix F.</i>
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	<i>Stability analysis and a summary of elevation discharge data was provided by Bureau of Operations.</i>
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	<i>Only boring records available.</i>
POST-CONSTRUCTION SURVEYS OF DAM	<i>None</i>
BORROW SOURCES	<i>N/A</i>

ITEM	REMARKS
MONITORING SYSTEMS	None
MODIFICATIONS	None
HIGH POOL RECORDS	None
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	None
MAINTENANCE OPERATION RECORDS	Maintained by Bureau of Operations

ITEM	REMARKS
SPILLWAY PLAN	Appendix E.
SECTIONS	
DETAILS	

OPERATING EQUIPMENT  
PLANS & DETAILS

MISCELLANEOUS


Information in DER, Dams and Waterways Management, files concerning new Flat Rock Dam.

1. Maps and correspondence concerning the transfer of ownership of canal wall and canal to the City of Philadelphia.
2. "Report Upon the Application of the Office of Resources Management" prepared by state, dated July 16, 1974.



**APPENDIX**

**C**



PHOTOGRAPH LOCATION PLAN  
FLAT ROCK DAM

PLATE C-1



RIGHT ABUTMENT AREA WITH GROUTED  
RIPRAP.

PHOTOGRAPH NO. 1




UPSTREAM RIGHT ABUTMENT.

PHOTOGRAPH NO. 2



LEFT END OF DAM ABUTS CANAL WALL  
OWNED BY THE CITY OF PHILADELPHIA.

PHOTOGRAPH NO. 3



LEFT ABUTMENT FROM UPSTREAM SIDE.  
STONE FORMED ABUTMENT FOR ORIGINAL  
FLAT ROCK DAM, A TIMBER CRIB STRUCTURE.



CANAL WALL IMMEDIATELY DOWNSTREAM OF  
THE DAM.


PHOTOGRAPH NO. 5



OVERFLOW WEIR OF CANAL WALL.

PHOTOGRAPH NO. 6





INLET HOUSE WHICH FORMALLY CONTROLLED  
FLOW TO LOCKS.

PHOTOGRAPH NO. 7




SHEET PILING CUTOFF TO CANAL.

PHOTOGRAPH NO. 8




VIEW OF DOWNSTREAM SIDE OF CANAL  
WALL NEAR INLET HOUSE.

PHOTOGRAPH NO. 9




JOINT DETERIORATION ON CANAL WALL NEAR  
DAM ABUTMENT.

PHOTOGRAPH NO. 10




VERTICAL DISPLACEMENT BETWEEN  
CONSTRUCTION JOINTS, APPARENTLY  
AS CONSTRUCTED.

PHOTOGRAPH NO. 11



SPALLING IN CANAL WALL WEIR.

PHOTOGRAPH NO. 12



TYPICAL JOINT DETERIORATION OF  
CONSTRUCTION JOINTS.

PHOTOGRAPH NO. 13



BUILDING ABOUT 8,000 FEET DOWNSTREAM  
OF DAM. FIRST FLOOR IS ABOUT 18 FEET  
ABOVE WATER LEVEL.

PHOTOGRAPH NO. 14





CANOE CLUB AT CONFLUENCE OF  
WISSAHICKON CREEK AND SCHUYLKILL  
RIVER. FIRST FLOOR 15 FEET  
ABOVE WATER LEVEL.

PHOTOGRAPH NO. 15

## **APPENDIX**

**D**

BY MES DATE 7/23/80  
CHKD. BY SEM DATE 7/28/80

SUBJECT Flat Rock Dam  
Hydrology / Hydraulics

SHEET 2 OF 5  
JOB No. \_\_\_\_\_

### Classification (Ref. Recommended Guidelines for Safety Inspection of Dams)

1. The hazard classification is rated as "High" as there would be economic loss and loss of life in the event of a sudden failure of the dam not during an extreme event.
2. The size classification is "Intermediate" based on its estimated 1500 Ac.-ft. total storage capacity and less than 100 ft. height.
3. The selected spillway design flood, based on size and hazard classification, is the PMF (Probable Maximum Flood), less than the recommended PMF.

### Hydrology and Hydraulic Analysis

#### 1. Original Data

As the concrete dam replaces an old timber crib structure, limited hydrologic/hydraulic analysis was performed. Original hydraulic analysis indicated that flows of 125,000 cfs would increase the tail-water elevation to 50.6, 0.3 ft below the pool elevation and flows exceeding 130,000 cfs would submerge the weir.


#### 2. Evaluation Data

The inflow hydrograph shown on sheet 3, was supplied by the Corps of Engineers, Philadelphia District, as the SPF (Standard Project Flood) for the downstream Fairmount Dam drainage area of 1893 square miles. The flows at Flat Rock Dam will be somewhat less, as Flat Rock Dam drainage area is 1809 square miles. Reduce flows by  $(1809/1893)^{0.67}$ .

The elevation-discharge data, shown on sheet 4, was supplied by DER, Bureau of Design.

SPF HYDROGRAPH DEVELOPED FOR  
DOWNSTREAM FAIRMOUNT DAM  
REDUCED FOR THE SMALLER  
FLAT ROCK DAM DRAINAGE AREA

$Q_p = 225,700$  CFS  
ASSUME SPF = 0.5 PMF



BY MEB DATE 7/23/80  
 CHKD. BY REM DATE 7/28/80

SUBJECT Flat Rock Dam  
Hydrology / Hydraulics

SHEET 4 OF 5  
 JOB No. \_\_\_\_\_

Flat Rock Dam  
Weir Summary Data

<u>Discharge (cfs)</u>	<u>Upstream Pool Elev.</u>	<u>Pool Energy Grade Elev.</u>	<u>Tail Water Elev.</u>
30,000	44.0	44.5	31.7
40,000	45.1	45.7	35.6
50,000	46.2	47.1	38.6
60,000	47.0	48.3	41.1
70,000	47.8	49.3	43.2
80,000	48.7	50.3	45.0
90,000	49.4	51.2	46.5
98,000	50.0	51.9	47.7
110,000	50.5	53.0	49.3
120,000	50.9	53.7	50.6
130,000	51.8	54.5	51.8

Weir Crest 32.7  
 Notches 32.2

the above supplied by Bureau of Design (DER)

$H_0 = 14.5$  ft (design head), confirmed by as-built  
 shape of weir

$L = 510$  ft. from as built drawing

at  $H_0$  (total head on crest) = 8 ft

$$H_0/H_0 = 8/14.5 = 0.55$$

$C/C_0 = 0.93$  Ref. Design of Small Dams, Bureau of  
 Reclamation, 2nd ed., p. 378

$P \sim 5$  ft, because old dam not completely removed

$$P/H_0 = 5/14.5 = 0.34$$

$$C_0 = 3.67$$

$$Q = 3.67 \cdot 0.93 \cdot 510 \cdot 8^{1.5}$$

$$= 39,400 \text{ cfs} \sim 40,000 \text{ listed above}$$

BY NEB DATE 2/23/80

SUBJECT

SHEET 5 OF 5HKB BY NEB DATE 2/23/80Flat Rock Dam

JOB No.

hydrology, hydraulics


Considering the size of the watershed, available flood water storage by Flat Rock Dam is very limited. Therefore, assume no attenuation of flood hydrograph shown on sheet 3.

Assume the SDF (sheet 3) to be the PMF.


The left abutment elevation is 40.8, adjacent to the existing gravity canal wall at 44.8. The right abutment elevation is 44.2. A pool elevation of 44.0 ft results in a weir discharge of about 30,000 cfs, or about 0.07 PMF.

**APPENDIX**


**E**







LIMITS OF  
SCHUYLKILL RIVER  
BASIN



ON COUNTY

LEHIGHTON

LEHIGH COUNTY

BETHLEHEM

ALLENTOWN

QUAKERTOWN

MONTGOMERY COUNTY

POTTSTOWN

ROYERSFORD

PHOENIXVILLE

NORRISTOWN

CONSHOHOCKEN

WEST CONSHOHOCKEN

BRIDGEPORT

COATESVILLE

WEST CHESTER

DELAWARE

CHESTER

PENNA.

DELAWARE

NEW JERSEY

PENNSYLVANIA

SCHUYLKILL  
RIVER BASIN

LOCATION MAP

SCALE IN MILES



HYDROLOGIC MAP


FLAT ROCK DAM

NAT.I.D.NO.PA.00896

PHILADELPHIA CO

DATA OBTAINED FROM DER WATER RESOURCES BULL  
NO.4 WATER RESOURCES SURVEY, THE SCHUYLKILL  
PA.


PLATE




# COMMONWEALTH OF PENNSYLVANIA LEASES AND AGREEMENTS

1914-10-1878 WEST MANHATTAN GAS & LIGHT CO. GAS PIPES  
1931 11-15-25 CONTAINER CORPORATION OF AMERICA WHARF & CONVEYOR ON STEEL TOWER  
1920 3-16-1925 PHILADELPHIA ELECTRIC COMPANY 3 OPEN WIRES & GROUND WIRES  
NO. 1725 30,000 BOND 12-5-1886 CITY OF PHILADELPHIA MANTURE INTERCEPT SEWER  
NO. 123 SECT. 7 MAPS 318480 7-10-41 COMMONWEALTH OF PENNSYLVANIA RIGHT OF PASSAGE  
10861 3-1-42 CONTAINER CORPORATION OF AMERICA CROSSING TOW PATH & TRACES


NOTE: THESE DRAWINGS WERE MADE FROM READING RAILROAD, CONTAINER  
CORPORATION OF AMERICA & PROPERTY BOOK OF SCH'L NAVIGATION CO.  
DATED 1860





2

PLA




PHILADELPHIA



LOCATION MAP

SCHUYLKILL CANAL



SITE PLAN

SCHUYLKILL RIVER

TRAVERSE DATA


Station	Station	Station	Station
4+77.576	4+77.576	4+77.576	4+77.576
6+50.718	6+50.718	6+50.718	6+50.718
8+04.888	8+04.888	8+04.888	8+04.888
10+74.388	10+74.388	10+74.388	10+74.388
14+72.848	14+72.848	14+72.848	14+72.848
18+07.888	18+07.888	18+07.888	18+07.888
21+04.888	21+04.888	21+04.888	21+04.888
24+27.848	24+27.848	24+27.848	24+27.848
28+63.188	28+63.188	28+63.188	28+63.188
31+19.768	31+19.768	31+19.768	31+19.768

LEGEND

- Core Sample
- Station and/or Core Sample
- Proposed Grade Elevation
- Elevation of Top of Existing Dam
- Existing Structure to Remain
- Boundary of Island

THE GENERAL STATE AUTHORITY	
PROJECT NO. G. S. A. 100-27	
FLAT ROCK DAM	
SCHUYLKILL RIVER PROJECT	
APPROVED BY THE BOARD OF SUPERVISORS	
DEPARTMENT OF ENVIRONMENTAL RESOURCES	
OFFICE OF RESOURCE MANAGEMENT	
GENERAL PLAN	
DATE	BY
1967	100-27
S-1	

2



SCHUYLKILL RIVER

PLAN  
Scale 1" = 100'

PROFILE

Scale 1" = 20'  
(vert. 1" = 10')

GENERAL NOTES

- Profile prepared from construction stage of high water existing condition.
- Stationing taken along 4' of high water.
- S.S. 1112 Monument No. 9 1112 010 on existing right of way line.
- Section A-A' per plan view and in the center line from excavator and other work shall be located in the center line.
- Top of dam to be 4'.
- Section A-A' and B-B' shown existing conditions.
- Section C-C' shown Section A-A' and B-B' and center line of dam.
- The contract shall observe the Act, Section 1000, as amended in paragraph 40 thru 42, Section and Supplemental Contract paragraphs 40 thru 42 and the Act of Legislature passed in 1917 (Act No. 27) of the General Assembly.

ELEVATION

FRONT DETAIL

BARRIAGE


LAND POST

THE GENERAL STATE AUTHORITY	
PROJECT NO. G.S.A. 100-27	
FLAT ROCK DAM	
SCHUYLKILL RIVER PROJECT	
DEPARTMENT OF HYDROLOGICAL ENGINEERING	
OFFICE OF SURVEYING AND MAPPING	
PLAN AND PROFILE	
DATE	NO. 2
BY	S-2


2

PLATE 4







ELEVATION



REINFORCEMENT DETAILS



CONTRACTION JOINT DETAIL




LAYOUT AND CONSTRUCTION JOINT DETAILS

LOW FLOW WEIR

Scale 3/4" = 1'-0"

CIRCULAR LAYOUT  
CONSTRUCTION JOINT DETAIL

Scale 3/4" = 1'-0"



REINFORCEMENT DETAILS  
SEE SHEET


WEIR COORDINATES

Station	Elevation	Station	Elevation
784	2.70	270	2.70
785	2.70	271	2.70
786	2.70	272	2.70
787	2.70	273	2.70
788	2.70	274	2.70
789	2.70	275	2.70
790	2.70	276	2.70
791	2.70	277	2.70
792	2.70	278	2.70
793	2.70	279	2.70
794	2.70	280	2.70
795	2.70	281	2.70
796	2.70	282	2.70
797	2.70	283	2.70
798	2.70	284	2.70
799	2.70	285	2.70
800	2.70	286	2.70
801	2.70	287	2.70
802	2.70	288	2.70
803	2.70	289	2.70
804	2.70	290	2.70
805	2.70	291	2.70
806	2.70	292	2.70
807	2.70	293	2.70
808	2.70	294	2.70
809	2.70	295	2.70
810	2.70	296	2.70
811	2.70	297	2.70
812	2.70	298	2.70
813	2.70	299	2.70
814	2.70	300	2.70
815	2.70	301	2.70
816	2.70	302	2.70
817	2.70	303	2.70
818	2.70	304	2.70
819	2.70	305	2.70
820	2.70	306	2.70
821	2.70	307	2.70
822	2.70	308	2.70
823	2.70	309	2.70
824	2.70	310	2.70
825	2.70	311	2.70
826	2.70	312	2.70
827	2.70	313	2.70
828	2.70	314	2.70
829	2.70	315	2.70
830	2.70	316	2.70
831	2.70	317	2.70
832	2.70	318	2.70
833	2.70	319	2.70
834	2.70	320	2.70
835	2.70	321	2.70
836	2.70	322	2.70
837	2.70	323	2.70
838	2.70	324	2.70
839	2.70	325	2.70
840	2.70	326	2.70
841	2.70	327	2.70
842	2.70	328	2.70
843	2.70	329	2.70
844	2.70	330	2.70
845	2.70	331	2.70
846	2.70	332	2.70
847	2.70	333	2.70
848	2.70	334	2.70
849	2.70	335	2.70
850	2.70	336	2.70
851	2.70	337	2.70
852	2.70	338	2.70
853	2.70	339	2.70
854	2.70	340	2.70
855	2.70	341	2.70
856	2.70	342	2.70
857	2.70	343	2.70
858	2.70	344	2.70
859	2.70	345	2.70
860	2.70	346	2.70
861	2.70	347	2.70
862	2.70	348	2.70
863	2.70	349	2.70
864	2.70	350	2.70
865	2.70	351	2.70
866	2.70	352	2.70
867	2.70	353	2.70
868	2.70	354	2.70
869	2.70	355	2.70
870	2.70	356	2.70
871	2.70	357	2.70
872	2.70	358	2.70
873	2.70	359	2.70
874	2.70	360	2.70
875	2.70	361	2.70
876	2.70	362	2.70
877	2.70	363	2.70
878	2.70	364	2.70
879	2.70	365	2.70
880	2.70	366	2.70
881	2.70	367	2.70
882	2.70	368	2.70
883	2.70	369	2.70
884	2.70	370	2.70
885	2.70	371	2.70
886	2.70	372	2.70
887	2.70	373	2.70
888	2.70	374	2.70
889	2.70	375	2.70
890	2.70	376	2.70
891	2.70	377	2.70
892	2.70	378	2.70
893	2.70	379	2.70
894	2.70	380	2.70
895	2.70	381	2.70
896	2.70	382	2.70
897	2.70	383	2.70
898	2.70	384	2.70
899	2.70	385	2.70
900	2.70	386	2.70
901	2.70	387	2.70
902	2.70	388	2.70
903	2.70	389	2.70
904	2.70	390	2.70
905	2.70	391	2.70
906	2.70	392	2.70
907	2.70	393	2.70
908	2.70	394	2.70
909	2.70	395	2.70
910	2.70	396	2.70
911	2.70	397	2.70
912	2.70	398	2.70
913	2.70	399	2.70
914	2.70	400	2.70
915	2.70	401	2.70
916	2.70	402	2.70
917	2.70	403	2.70
918	2.70	404	2.70
919	2.70	405	2.70
920	2.70	406	2.70
921	2.70	407	2.70
922	2.70	408	2.70
923	2.70	409	2.70
924	2.70	410	2.70
925	2.70	411	2.70
926	2.70	412	2.70
927	2.70	413	2.70
928	2.70	414	2.70
929	2.70	415	2.70
930	2.70	416	2.70
931	2.70	417	2.70
932	2.70	418	2.70
933	2.70	419	2.70
934	2.70	420	2.70
935	2.70	421	2.70
936	2.70	422	2.70
937	2.70	423	2.70
938	2.70	424	2.70
939	2.70	425	2.70
940	2.70	426	2.70
941	2.70	427	2.70
942	2.70	428	2.70
943	2.70	429	2.70
944	2.70	430	2.70
945	2.70	431	2.70
946	2.70	432	2.70
947	2.70	433	2.70
948	2.70	434	2.70
949	2.70	435	2.70
950	2.70	436	2.70
951	2.70	437	2.70
952	2.70	438	2.70
953	2.70	439	2.70
954	2.70	440	2.70
955	2.70	441	2.70
956	2.70	442	2.70
957	2.70	443	2.70
958	2.70	444	2.70
959	2.70	445	2.70
960	2.70	446	2.70
961	2.70	447	2.70
962	2.70	448	2.70
963	2.70	449	2.70
964	2.70	450	2.70
965	2.70	451	2.70
966	2.70	452	2.70
967	2.70	453	2.70
968	2.70	454	2.70
969	2.70	455	2.70
970	2.70	456	2.70
971	2.70	457	2.70
972	2.70	458	2.70
973	2.70	459	2.70
974	2.70	460	2.70
975	2.70	461	2.70
976	2.70	462	2.70
977	2.70	463	2.70
978	2.70	464	2.70
979	2.70	465	2.70
980	2.70	466	2.70
981	2.70	467	2.70
982	2.70	468	2.70
983	2.70	469	2.70
984	2.70	470	2.70
985	2.70	471	2.70
986	2.70	472	2.70
987	2.70	473	2.70
988	2.70	474	2.70
989	2.70	475	2.70
990	2.70	476	2.70
991	2.70	477	2.70
992	2.70	478	2.70
993	2.70	479	2.70
994	2.70	480	2.70
995	2.70	481	2.70
996	2.70	482	2.70
997	2.70	483	2.70
998	2.70	484	2.70
999	2.70	485	2.70
1000	2.70	486	2.70


NOTES

1. Elevations for low flow weir are 0.50 lower than corresponding elevations given in the above chart for "dry" conditions.
2. Concrete flush on weir shall be 0.50 ft. as applicable.
3. Reinforcing steel shall be 2" apart at all points.
4. All construction shall be in accordance with the specifications.



Project No. 100-27	
The General State Authority	
Project No. G.S.A. 100-27	
Flat Rock Dam	
Schuykill River Project	
Department of Environment, Planning & Resources	
Office of Resources Management	
Weir Details	
S-3	
















STA 0+258 TO 0+338  
SECTIONS - RAMP B







THE GENERAL STATE AUTHORITY PROJECT NO. G.S.A. 100-27 FLAT ROCK DAM SCHUYLKILL RIVER PROJECT DEPARTMENT OF ENVIRONMENTAL RESOURCES OFFICE OF RESOURCE MANAGEMENT	
RIGHT ABUTMENT SECTIONS	
Date: 10/1/78 By: [Signature]	Sheet: 1 of 1 S-6

2






PLAN





ELEVATION






LEFT ABUTMENT WALL MODIFICATION




Scale 1/4\"/>











Empty Room      No. 10089      No. 10089      No. 10089  
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100 101 102 103 104 105 106 107 108 109 110 111 112 113 114 115 116 117 118 119 120 121 122 123 124 125 126 127 128 129 130 131 132 133 134 135 136 137 138 139 140 141 142 143 144 145 146 147 148 149 150 151 152 153 154 155 156 157 158 159 160 161 162 163 164 165 166 167 168 169 170 171 172 173 174 175 176 177 178 179 180 181 182 183 184 185 186 187 188 189 190 191 192 193 194 195 196 197 198 199 200 201 202 203 204 205 206 207 208 209 210 211 212 213 214 215 216 217 218 219 220 221 222 223 224 225 226 227 228 229 230 231 232 233 234 235 236 237 238 239 240 241 242 243 244 245 246 247 248 249 250 251 252 253 254 255 256 257 258 259 260 261 262 263 264 265 266 267 268 269 270 271 272 273 274 275 276 277 278 279 280 281 282 283 284 285 286 287 288 289 290 291 292 293 294 295 296 297 298 299 300 301 302 303 304 305 306 307 308 309 310 311 312 313 314 315 316 317 318 319 320 321 322 323 324 325 326 327 328 329 330 331 332 333 334 335 336 337 338 339 340 341 342 343 344 345 346 347 348 349 350 351 352 353 354 355 356 357 358 359 360 361 362 363 364 365 366 367 368 369 370 371 372 373 374 375 376 377 378 379 380 381 382 383 384 385 386 387 388 389 390 391 392 393 394 395 396 397 398 399 400 401 402 403 404 405 406 407 408 409 410 411 412 413 414 415 416 417 418 419 420 421 422 423 424 425 426 427 428 429 430 431 432 433 434 435 436 437 438 439 440 441 442 443 444 445 446 447 448 449 450 451 452 453 454 455 456 457 458 459 460 461 462 463 464 465 466 467 468 469 470 471 472 473 474 475 476 477 478 479 480 481 482 483 484 485 486 487 488 489 490 491 492 493 494 495 496 497 498 499 500 501 502 503 504 505 506 507 508 509 510 511 512 513 514 515 516 517 518 519 520 521 522 523 524 525 526 527 528 529 530 531 532 533 534 535 536 537 538 539 540 541 542 543 544 545 546 547 548 549 550 551 552 553 554 555 556 557 558 559 560 561 562 563 564 565 566 567 568 569 570 571 572 573 574 575 576 577 578 579 580 581 582 583 584 585 586 587 588 589 590 591 592 593 594 595 596 597 598 599 600 601 602 603 604 605 606 607 608 609 610 611 612 613 614 615 616 617 618 619 620 621 622 623 624 625 626 627 628 629 630 631 632 633 634 635 636 637 638 639 640 641 642 643 644 645 646 647 648 649 650 651 652 653 654 655 656 657 658 659 660 661 662 663 664 665 666 667 668 669 670 671 672 673 674 675 676 677 678 679 680 681 682 683 684 685 686 687 688 689 690 691 692 693 694 695 696 697 698 699 700 701 702 703 704 705 706 707 708 709 710 711 712 713 714 715 716 717 718 719 720 721 722 723 724 725 726 727 728 729 730 731 732 733 734 735 736 737 738 739 740 741 742 743 744 745 746 747 748 749 750 751 752 753 754 755 756 757 758 759 760 761 762 763 764 765 766 767 768 769 770 771 772 773 774 775 776 777 778 779 780 781 782 783 784 785 786 787 788 789 790 791 792 793 794 795 796 797 798 799 800 801 802 803 804 805 806 807 808 809 810 811 812 813 814 815 816 817 818 819 820 821 822 823 824 825 826 827 828 829 830 831 832 833 834 835 836 837 838 839 840 841 842 843 844 845 846 847 848 849 850 851 852 853 854 855 856 857 858 859 860 861 862 863 864 865 866 867 868 869 870 871 872 873 874 875 876 877 878 879 880 881 882 883 884 885 886 887 888 889 890 891 892 893 894 895 896 897 898 899 900 901 902 903 904 905 906 907 908 909 910 911 912 913 914 915 916 917 918 919 920 921 922 923 924 925 926 927 928 929 930 931 932 933 934 935 936 937 938 939 940 941 942 943 944 945 946 947 948 949 950 951 952 953 954 955 956 957 958 959 960 961 962 963 964 965 966 967 968 969 970 971 972 973 974 975 976 977 978 979 980 981 982 983 984 985 986 987 988 989 990 991 992 993 994 995 996 997 998 999 1000 1001 1002 1003 1004 1005 1006 1007 1008 1009 1010 1011 1012 1013 1014 1015 1016 1017 1018 1019 1020 1021 1022 1023

### ROLLING LEGEND

**DISPATCH AND RETURN**

[illegible]

DATE		PAGE	
NO. 10474		OF 10	
<p><i>2-10-64</i></p> <p><i>44-4-64</i></p> <p><i>2-10-64</i></p>			
<p>PROJECT NO. 63 A100-2</p>			
<p>FLAT ROCK DAM SCHUYLKILL RIVER PROJECT</p>			
<p>COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF COMMERCE, MARINE OFFICE OF REVENUE AND CUSTOMS</p>			
<p>SUBSURFACE EXPLORATION AND HYDROGRAPHY</p>			
APPROVED BY	DATE	APPROVED BY	DATE
<i>AL</i>	<i>2-10-64</i>	<i>AL</i>	<i>2-10-64</i>
APPROVED BY	DATE	APPROVED BY	DATE
<i>AL</i>	<i>2-10-64</i>	<i>AL</i>	<i>2-10-64</i>

**APPROXIMATE CROSS SECTION  
OF CANAL WALL**



**APPENDIX**

**F**



SITE GEOLOGY  
FLAT ROCK DAM

Flat Rock Dam is located in the Piedmont Uplands Section of the Piedmont Physiographic Province. As shown in Plate F-1, the dam is underlain by the Wissahickon Formation of Lower Paleozoic age. An excellent exposure of gneissic schist occurs above the river bank in line with the left dam abutment. Rock foliation at this point strikes N65°W (oblique to dam centerline) and dips 15 degrees to the northeast. Minor rock jointing observed strikes N85°W and dips downstream at 81 degrees (near vertical) to the south. Exposures of the Wissahickon Formation occur in the vicinity of both dam abutments and downstream of the dam within the Schuylkill River. The dam is therefore most likely entirely founded upon the gneissic schist bedrock.



AD-A091 497

WOODWARD-CLYDE CONSULTANTS PLYMOUTH MEETING PA  
NATIONAL DAM INSPECTION PROGRAM. FLAT ROCK DAM  
AUG 80 M F BECK, J F FREDERICK

F/G 13/13  
(NDS I.D. NUMBER--ETC(U)  
DACW31-80-C-0018

NL

UNCLASSIFIED

2 2

3 4




END

DATE

FILED

'2 80

DTIC



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963 A

**APPENDIX**

**G**

# DESIGN CALCULATIONS

<b>Woodward-Clyde Consultants</b> Consulting Engineers, Geologists and Environmental Scientists	Owner:	Page <u>1</u> of <u>5</u>
	Project:	Job No./File No.
System:	Calculator <u>R.B. Mackey</u> Date <u>2-24-80</u>	
Calculation for:	<u>Stability</u>	Reviewer <u>MEB</u> Date <u>2/22/80</u>

## Dam

Calculations of dam stability from State files were reviewed:

Calculations 7/13 - 7/18/73 for original design proposal for new dam

Calculations 2/27 - 3/1/75 for revised design

"Supplemental Structural Report, Flat Rock Dam..."  
3/10/75 - 1 page

Overturning - calculations for designed section showed a minimum safety factor of 1.45 for the condition of 18.8' of water over crest. Related calculations for original design without anchor bars showed a similar safety factor and the resultant of forces being within the middle 1/3 of dam base. Maximum foundation pressures were shown to be less than 4,000 psf.

Sliding - Calculations for weir section showed a minimum safety factor of 1.46 for the condition of 6.3' of water over the crest. The calculations are based entirely upon friction as the resisting force and do not include adhesion between the concrete and the foundation rock.

From State analysis  $\Sigma F_x = 14,115 \text{ lb/ft}$  Coef. friction = 0.7  
 $\Sigma F_y = 29,407 \text{ lb/ft}$

Use adhesion = 40 psi = 5,760 psf (min. value ETZ 1110-2-1973)

$$F.S. = \frac{29,407 \times 1.7 + 5,760 \times 34}{14,115} = \underline{15.3} > 4$$

# DESIGN CALCULATIONS

<b>Woodward-Clyde Consultants</b> Consulting Engineers, Geologists and Environmental Scientists	Owner:	Page <u>2</u> of <u>5</u>
	Project: <u>Flat Rock Dam</u>	Job No./File No.
System:		Calculator <u>R. E. Bailey</u> Date <u>7-28-88</u>
Calculation for: <u>Stability</u>		Reviewer <u>MEB</u> Date <u>7/22/88</u>

## Canal Wall

### Assumptions

Unit weight of concrete = 150 pcf ✓  
 Unit weight of water = 62.4 pcf ✓  
 Submerged weight of silt = 40 pcf ✓  
 Submerged weight of soil = 60 pcf ✓  
 Earth pressure coefficient  
     of silt and soil = 0.5 ✓  
 Friction coefficient of rock  
     and concrete to rock = 0.7 ✓  
 Compressive strength of rock = 1,000 psi

### Analysis Condition

From hydrology/hydraulic analysis, dam and canal  
 wall will be completely submerged during  
 0.5 PMF event. Therefore, critical condition  
 for maximum net horizontal force on canal  
 wall will be during a lesser magnitude event  
 when tail water is much lower.

Use conditions of discharge = 30,000 cfs.

This is consistent with lowest safety factor for dam.

$$Q = 30,000 \text{ cfs} \approx 0.07 \text{ PMF}$$

Reservoir Level = 44.0 (6.3' above crest)

Tail Water El. = 31.7  
(Appendix D)


For conservatism, ignore lateral pressure of tail water due to possible turbulence

# DESIGN CALCULATIONS

<b>Woodward-Clyde Consultants</b> Consulting Engineers, Geologists and Environmental Scientists	Owner:	Page <u>3</u> of <u>6</u>
	Project:	Job No./File No.
System:	Calculator <u>KEB</u> Date <u>2-24-80</u>	
Calculation for:	<u>Stability</u> Reviewer <u>MEB</u> Date <u>2/22/80</u>	

## Cross Section and Loadings

Use low section of wall at maximum height above river bed - location approximately 350' from dam center line.





# DESIGN CALCULATIONS

<b>Woodward-Clyde Consultants</b> Consulting Engineers, Geologists and Environmental Scientists	Owner:	Page <u>4</u> of <u>5</u>
	Project:	Job No./File No.
System:	Calculator <u>R. G. M. B. R.</u> Date <u>2-24-80</u>	
Calculation for:	<u>Stability</u> Reviewer <u>M.E.B.</u> Date <u>2/22/80</u>	

## Weights and Forces

Wall.  $C_1 = 6 \times 9 \times 150 = 8,100' \text{ lb/ft}$   
 $C_2 = \frac{1}{2} \times 9 \times 2 \times 150 = 1,350'$   
 $C_3 = 8 \times 19 \times 150 = 22,800'$   
 $C_4 = \frac{1}{2} \times 7.5 \times 19 \times 150 = 10,687.5'$   
 Uplift  $U_1 = 17.2 \times 62.4 \times 15.5 = 16,635.8'$   
 $U_2 = \frac{1}{2} \times 12.3 \times 62.4 \times 15.5 = 5,948.3'$   
 Water  $W_1 = \frac{1}{2} \times 29.5 \times 62.4 = 27,151.8'$   
 Silt  $S_1 = \frac{1}{2} (\frac{1}{2} \times 40) 5^2 = 250'$   
 $S_2 = (\frac{1}{2} \times 40) \times 5 \times 14 = 1,400'$   
 Soil  $S_3 = \frac{1}{2} (\frac{1}{2} \times 60) 14^2 = 2,940'$

$\Sigma F_y \quad C_1 + C_2 + C_3 + C_4 - U_1 - U_2 = 20,353.4 \text{ lb/ft} \quad \checkmark$

## Moments about toe

$\Sigma M_{\curvearrowright} \quad C_1 \times M_{C1} = 8,100 \times 12.5' = 101,250' \text{ ft-lb/ft}$   
 $C_2 \times M_{C2} = 1,350 \times 8.8' = 11,880'$   
 $C_3 \times M_{C3} = 22,800 \times 11.5' = 262,200'$   
 $C_4 \times M_{C4} = 10,687.5 \times 5' = 53,437.5'$   
 $\underline{428,767.5'}$

$\Sigma M_{\curvearrowleft} \quad U_1 \times M_{U1} = 16,635.8 \times 7.75' = 128,927.5' \text{ ft-lb/ft}$   
 $U_2 \times M_{U2} = 5,948.3 \times 10.33' = 61,445.9'$   
 $W_1 \times M_{W1} = 27,151.8 \times 9.83' = 266,902.2'$   
 $S_1 \times M_{S1} = 250 \times 15.67' = 3,917.5'$   
 $S_2 \times M_{S2} = 1,400 \times 7' = 9,800.0'$   
 $S_3 \times M_{S3} = 2,940 \times 4.67' = 13,729.8'$   
 $\underline{484,722.9'}$

Net moment =  $55,955.4' \quad \checkmark$

# DESIGN CALCULATIONS

<b>Woodward-Clyde Consultants</b> Consulting Engineers, Geologists and Environmental Scientists	Owner:	Page <u>5</u> of <u>5</u>
	Project: <u>Flat Rock Dam</u>	Job No./File No.
System:	Calculator <u>R.E. Padley</u> Date <u>2-24-80</u>	
Calculation for: <u>Stability</u>	Reviewer <u>REB</u> Date <u>2/22/80</u>	

## Location of Resultant

$$X = \frac{\sum M}{\sum F_y} = \frac{(-) 55,955.4}{20,353.4} = (-) 2.75'$$

Resultant is 2.75' beyond toe of wall

Add tail water to analysis

$$\begin{aligned}
 W_{2v} &= 0.5 \times 17.2 \times 7.09 \times 62.4 = 3804.8 \text{ lb/ft} \\
 W_2 &= \frac{1}{2} \times 17.2^2 \times 62.4 = 9,230.2 \text{ lb/ft} \\
 \sum M \rightarrow + & \quad + W_{2v} \times x_{w2} = 3804.8 \times 2.36 = 8,992 \\
 & \quad + W_2 \times 1/3 W_2 = 9,230.2 \times 5.73 = 52,889.0 \\
 & \quad + 428,767.5 \\
 & \quad \underline{490,648.5}
 \end{aligned}$$

$$\sum M = 5929.6 (+)$$

$$\text{Resultant } X = \frac{(+ ) 5929.6}{24158} = 0.24'$$

Resultant is 0.24' inside the toe of wall

$$\sum F_x \quad W_1 + S_1 + S_2 + S_3 = 31,741.8 \text{ lb/ft}$$

$$\text{Sliding (friction)} \quad SF = \frac{\sum F_y (F)}{\sum F_x} = \frac{20,353.4 \times 0.7}{31,741.8} = \underline{\underline{0.45}}$$

include tail water

$$SF = \frac{24,158 \times 0.7}{(31,741.8 - 9,230.2)} = \underline{\underline{0.75}}$$

(friction + adhesion)

for adhesion, use 15% of rock compressive strength

$$SF = \frac{24,158 \times 0.7 + 0.15(1,000 \times 144) \times 15.5}{31,741.8 - 9,230.2}$$

$$\underline{\underline{SF = 15.6 > 4}}$$

# DESIGN CALCULATIONS

<b>Consultants</b> pers. Geologists metal Scientists	Owner:	Page <u>6</u> of <u>6</u>
	Project: <u>Flat Rock Dam</u>	Job No./File No.
		Calculator <u>MEB</u>
		Date <u>7/27/80</u>
		Reviewer <u>R.E. Mubg</u>
		Date <u>7/28/80</u>

stability

$$\text{pressure} = \frac{2}{3} \frac{\Sigma F_y}{e_T} \quad (e_T \text{ measured from toe})$$

assuming tailwater  $\Sigma F_y = 24,158.2$

$$\frac{2}{3} \frac{24,158.2}{0.24} =$$

$$\frac{2}{3} \frac{24,158}{7.51} = 67,105 \text{ psf}$$